

Project: St Andrews CP School

Construction: Refurbishment

Main Contractor: D Shawcross

Roof Area: 2200m²

St Andrews was an extremely sensitive contract as a high proportion of the work was carried out during term time. We developed a close working relationship with the school to ensure the work was carried out to guarantee the safety of all personnel internally as not to disturb or hinder their daily routines. Children and staff were decanted into alternative makeshift classrooms whilst the existing waterproofing was stripped and removed. Close liaisons with school management was the key and a minimum 24 hour notice period was given to the school prior to stripping, this practice allowed the roof to be sectioned into safe manageable portions thus keeping disruption to a minimum.

The whole of the perimeter edge had all the existing fascia renewed in a Marley Eternit Cladding to add a pleasant, decorative and weather resistant effect.

